BRUHATH BANGALORE MAHANAGARA PALIKE
Yelahanka Zone, Yelahanka Division

Executive Engineer
Yelahanka Division
BBMP, Bangalore-64

Approved Tender Schedule - B

Name of Work:-Construction of concrete drains and concrete roads at Basavalingappa Layout in Attur ward no-03.

Sl. No	Description	Unit	Approved qty	Approved Rate	
				Rate	Rate in words
1	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	172.35	83.16	Rupees eighty three and paise sixteen only
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m.	Cum	41.58	288.36	Rupees two hundred eighty eight and paise thirty six only
3	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.	Cum	29.43	5070.60	Rupees five thousand seventy and paise sixty only

4	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per	Cum	10.56	4135.32	Rupees four thousand one hundred thorty five and paise thirty two only
5	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum	9.90	4905.36	Rupees four thousand nine hundred five and paise thirty six only
6	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	26.40	99.36	Rupees ninety nine and paise thorty six only
7	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work	Cum	6.00	6198.12	Rupees six thousand one hundred ninety eight and paise twelve only
8	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0	Tonne ,s	0.66	70509.96	Rupees seven thousand five hundred nine and paise ninety six only

9	KSRB M2200-5.11.Design mix M20 with OPC cement @320 kgs,with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999 Reaffirmed-2008.etc as per specification&direction of the engineer incharge of work	Cum	24.59	6732.72	Rupees six thousand seven hudnrded thirty two and paise seventy two only
10	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator,HOM of machinery screed vibratory,power floater,blade and disk etc,,with all lead and lift etc as per specifications	Sqm	150.00	97.20	Rupees seven and paise twenty only
11	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine,generator&HOM of machinery,including cost of blade,coolant etc as per specifications as per specifications	Rmtr	20.00	124.20	Rupees one hundred twenty four and paise twenty only
12	KSRRB M100-1 Loading and un loading of stone boulder/Stoneaggregates/sand/ kanker/ Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader, dumping, turning for return trip,excluding time for haulage and return trip complete as per specifications	Cum	213.93	68.04	Rupees sixty eight and paise four only

Signature of the contractor

Executive Engineer
Yelahanka Division
BBMP, Bangalore-64